

Bid Schedule

21-Mar-22

County Street Gravity Sewer Replacement City of Monett, Missouri

All Construction activities shall comply with City of Monett standard construction specifications as shown on City website.

C&IP = Complete and In-place

Item No.	Qty.	Units	Item Description	Unit Price Dollars Cents	Extended Total Dollars Cents
1-1	1	LS	Connection To Existing Sanitary Sewer		
1-2	86	LF	0'-8' Trench & Compacted Backfill C&IP		
1-3	497	LF	0'-8' Trench & Compacted Granular Backfill C&IP		
1-4	583	LF	Install 8" SDR26 PVC Sewer Pipe, Pipe furnished by City, C&IP		
1-5	6	EA	Install 8"X4" PVC Tees, pipe material furnished by City, C&IP		
1-6	62	LF	Install 4" SCH 40 PVC w/ Granular Backfill, PVC pipe and fittings furnished by City, C&IP		
1-7	174	LF	Install 4" SCH 40 PVC Serv Lat, w/ Topsoil, Seed & Mulch, PVC pipe and fittings furnished by City, C&IP		
1-8	4	EA	4' Dia. MH, Precast Concrete Manholes w/ F&C furnished by City, C&IP		
1-9	583	LF	Air Test 8" Dia. Gravity Sewer Pipe, Complete		
1-10	4	EA	Vacuum Testing of MH, Complete		
1-11	185	SY	Pavement Repair, 6" thick, Type 1 Compacted Aggregate Base, C&IP		
1-12	350	SY	Asphalt Pavement Repair, BP-1 (3" min. thickness), C&IP		
1-13	25	SY	Pavement Repair for Driveways, 7" thk Concrete, Complete		
1-14	1	LS	Surface Restoration, Complete		
1-15	1	LS	Abandon existing sewer line, remove existing MH F&C, punch 4-1" dia holes in bottom of manholes, fill w granular rock, capp surface w/ 6" baserock and cover w 3" min thk asphalt, C&IP		
1-16	1	LS	Mobilization		

Total Bid Amount